

SEPTIC SYSTEM SCHEDULE OF VALUES April 2010

Costs are based on an average site with no significant limiting conditions that would effect construction. Additional funding will be considered if justified by specific site conditions. Additional funding will also be considered if unforeseen underground conditions are encountered. Contractor to notify CWC before additional work is done.

| ITEM | COMPONENT | COST | UNIT |
|---|---|-------------|-------------|
| Engineering | As required | | |
| Septic Tanks - Tank replacement only. Includes Mobilization / Demobilization. | | | |
| 1000 gal | Excavation, backfill, tank, bedding, misc. fittings, topsoil, seed, mulch, 12" riser, pump and decommission old tank , hand labor. | \$ 2,574 | EA |
| 1250 gal | Same as above | \$ 2,807 | EA |
| 1500 gal | Same as above | \$ 3,063 | EA |
| Septic Tank with complete systems -Mob./ Demobilization not included. | | | |
| 1000gal - | Excavation, backfill, tank, bedding, misc. fittings, topsoil, seed, mulch, 12" riser, pump and decommission old tank , hand labor. | \$ 2,280 | EA |
| 1250 gal | Same as above | \$ 2,499 | EA |
| 1500gal | Same as above | \$ 2,755 | EA |
| Pump Chambers | Excavation, backfill, tank, bedding, misc. fittings, topsoil, seed, mulch, pumps,controls, 12" riser,electric service, hand labor. | \$ 4,192 | EA |
| Siphons | Excavation, backfill, tank, bedding,flout,fittings, topsoil, seed mulch. | \$ 2,513 | EA |
| 4" Sch 40 PVC | Excavation, backfill, pipe, bedding, misc. fittings, topsoil, seed, mulch. | \$ 9.24 | LF |
| 2" Force main | Same as above except for pipe size. | \$ 8.85 | LF |
| D- Box, 10-holes | Excavation, backfill, box, bedding, misc. fittings, topsoil, seed, mulch. | \$ 524 | EA |
| Fill Material | Material cost, 1hr. haul and placement | | |
| | absorption fill | \$ 18.59 | CY |
| | random fill | \$ 15.12 | CY |
| | extra stone | \$ 26.78 | CY |
| | Added cost for extra haul, round trip | \$ 7.25 | CY/HR |
| Effluent filters | Internal | \$ 65 | EA |
| | External | \$ 175 | EA |
| Conventional absorption trench | | \$ 8.56 | LF |
| Absorption trench in fill | | \$ 7.96 | LF |
| Absortion beds | complete | \$ 3.81 | SF |
| Curtain drain | 36" average depth complete include restoration, filter fabric | \$ 13.57 | LF |
| Swales | 12" to 24" depth | \$ 3.73 | LF |
| Additional Restoration - grade, topsoil, seed, mulch | | \$ 0.60 | SF |

Please call for enhanced treatment system prices