

If you are a contractor that works in the watershed and you did not get a Schedule of Values by mail please contact Leo labuda at 845-586-1400 to request that you be put on our mailing list for contractor updates.

SEPTIC SYSTEM SCHEDULE OF VALUES April 2011

Costs are based on an average site with no significant limiting conditions that would effect construction. Additional funding will be considered if justified by specific site conditions. Additional funding will also be considered if unforeseen underground conditions are encountered. Contractor to notify CWC before additional work is done.

ITEM	COMPONENT	COST	UNIT
Engineering	As required (see design fee schedule)		
Septic Tanks - Tank replacement only. Includes Mobilization / Demobilization.			
1000 gal	Excavation, backfill, tank, bedding, misc. fittings, topsoil, seed, mulch, 12" riser, pump and decommission old tank , hand labor.	\$ 2,651	EA
1250 gal	Same as above	\$ 2,884	EA
1500 gal	Same as above	\$ 3,190	EA
Septic Tank with complete systems -Mob./ Demobilization not included.			
1000gal -	Excavation, backfill, tank, bedding, misc. fittings, topsoil, seed, mulch, 12" riser, pump and decommission old tank , hand labor.	\$ 2,355	EA
1250 gal	Same as above	\$ 2,564	EA
1500gal	Same as above	\$ 2,870	EA
Pump Chambers	Excavation, backfill, tank, bedding, misc. fittings, topsoil, seed, mulch, pumps,controls, 12" riser,electric service, hand labor.	\$ 4,484	EA
Siphons	Excavation, backfill, tank, bedding,flout,fittings, topsoil, seed mulch.	\$ 2,705	EA
4" Sch 40 PVC	Excavation, backfill, pipe, bedding, misc. fittings, topsoil, seed, mulch.	\$ 9.72	LF
2" Force main	Same as above except for pipe size.	\$ 9.34	LF
D- Box, 10-holes	Excavation, backfill, box, bedding, misc. fittings, topsoil, seed, mulch.	\$ 525	EA
Fill Material	Material cost, 1hr. haul and placement		
	absorption fill	\$ 19.05	CY
	random fill	\$ 15.29	CY
	extra stone	\$ 27.17	CY
	Added cost for extra haul, round trip	\$ 7.92	CY/HR
Effluent filters	Internal	\$ 77	EA
	External	\$ 175	EA
Conventional absorption trench		\$ 9.45	LF
Absorption trench in fill		\$ 8.85	LF
Absortion beds	complete	\$ 3.94	SF
Curtain drain	36" average depth complete include restoration, filter fabric	\$ 13.56	LF
Swales	12" to 24" depth	\$ 3.77	LF
Additional Restoration - grade, topsoil, seed, mulch		\$ 0.60	SF

* Please call for enhanced treatment system prices *